# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT14106

## APPROVED SCHEDULE - B

**No. E/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014**

**Improvements to Roads, Drains and Covering Slab at Chamundeshwari Layout 1st Main 2nd Cross Road in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of E RAMESHA ANAND | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 205.2 | Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 90.0 | Rupees Ninety Only |
| 2 | 34.2 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4550.0 | Rupees Four Thousand Five Hundred Fifty Only |
| 3 | 547.2 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Sqm | 270.0 | Rupees Two Hundred Seventy Only |
| 4 | 71.82 | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5800.0 | Rupees Five Thousand Eight Hundred Only |
| 5 | 43.09 | Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work | Qtl | 7500.0 | Rupees Seven Thousand Five Hundred Only |
| 6 | 205.2 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 598.0 | Rupees Five Hundred Ninety Eight Only |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

| | | | | | |
|---|---|---|---|---|---|
| 7 | 1140 | Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work | m | 30.0 | Rupees Thirty Only |
| 8 | 205.2 | Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work | Sqm | 800.0 | Rupees Eight Hundred Only |
| 9 | 194.94 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 69.39 | Rupees Sixty Nine and Thirty Nine Paise Only |

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**